

**Details for Marches Growth Hub Portal Tender Advertisement**

Main Title of project	Warehouse Extension to existing building with 25Ton overhead crane
Address	Unit 8 Beacon Road, Rotherwas, HR2 6JF
Value (approx.) <i>(If separate lots/ work packages please put approx. value of each)</i>	<ol style="list-style-type: none"> <li>1. Steel Frame Building Construction inc Cladding - £200,000 - £225,000.00</li> <li>2. Supply and Install 25T Overhead Crane - £50,000 - £60,000 Exc VAT</li> </ol>
Planned Start Date	Tuesday 1 <sup>st</sup> June 2021
Planned Finish Date	Thursday 30th September 2021
Deadline date for submission of completed tenders	Monday 19th April 2021
Summary of opportunity	<ol style="list-style-type: none"> <li>1. To supply, Erect and Install Steel frame building extension to existing building – W21.3m x L18.3m approx. 5000 sq ft including Foundation works, Cladding, Electrical works, Overhead Doors and Concrete Floor</li> <li>2. To supply, install and commission 25t double girder crane with remote control</li> </ol> <p align="center"><i>We will accept tenders responses for individual lots or for both projects</i></p>
Opportunity details	<ol style="list-style-type: none"> <li>1. Steel Frame Building Construction: <ul style="list-style-type: none"> <li><b>Type of building:</b> Portal Frame</li> <li>Designed to BS EN 5950 Industrial specification</li> <li>Manufactured to BS EN 1090 Execution Class 2</li> <li><b>Span :</b> 21.30m</li> <li><b>Length :</b> 18.30m in 3 No 6.10m bays</li> <li><b>Eaves :</b> 11.20m above FFL</li> <li><b>Bases :</b> 0.45m below FFL</li> <li><b>Roof:</b> Insulated Composite Panel inc 10% of floor area to be Triple Skin GRP Rooflights</li> <li><b>Cladding:</b> Insulated Composite Panel</li> <li><b>Section Overhead Doors:</b> <ul style="list-style-type: none"> <li>2 No 4.5m Wide x 5.0m High Insulated Sectional Overhead Door(s) located in gable end.</li> <li>1 No 4.5m Wide x 5.0m High Insulated Sectional Overhead Door(s) located in existing side.</li> </ul> </li> <li><b>Personnel Doors:</b> 2 number Steel Doors</li> <li><b>Internal Concrete Slab:</b> To Supply and Lay a consolidated hardcore base across the internal area of the building comprising 150mm hardcore and scalplings.</li> <li><b>Electrical Works:</b> To provide 10 low bay LED overhead lights and 10 415v 16amp sockets surrounding the unit with associated cable management to suit</li> </ul> </li> </ol>
Evaluation / Selection criteria	

**Details for Marches Growth Hub Portal Tender Advertisement**

	<p>2. 25T Overhead Crane:</p> <p><b>Type of crane</b> : Double Girder crane <b>Bridge construction</b> Box beam <b>Safe Working Load (SWL)</b> 25,000 kg <b>Span (nominal rail centres)</b> 18,000 mm <b>Remote Control</b> <b>Install and Commission</b></p> <p>Price (90%) Delivery proposals &amp; ability to schedule work in accordance with project timeline (10%).</p> <p>.</p> <p><b>For the specification to Quote please contact Anthony Bushnell on 01432 346580 or email <a href="mailto:anthony.bushnell@selmach.com">anthony.bushnell@selmach.com</a></b></p>
--	---